

NOTE:  
PROVIDE BUILT-UP WOOD STUD POST EQUAL TO STUD DEPTH x WIDTH OF BEAM, AT BOTH ENDS OF STEEL OR WOOD BEAMS UNLESS NOTED OTHERWISE.



LINEEL NOTE:  
PROVIDE 2-2x8 ABOVE ALL MAIN FLOOR EXTERIOR DOORS AND WINDOWS, U.N.O.



HANDRAIL NOTE:  
PROVIDE CONTINUOUS HANDRAIL THROUGHOUT THE LENGTH OF STAIR AS PER 9.8.7.2 OF THE O.B.C 2006

FRAMING NOTES:  
ALL INTERIOR STUD WALLS TO BE 2x4, U.N.O.

PROVIDE DOUBLE JOIST FRAMING UNDER ALL PARALLEL WALLS ABOVE

NOTE:  
6 1/2" EXTERIOR WALL DIMENSION INCLUDES 1" OF INSULATED SHEATHING (OUTSIDE FACE IN LINE WITH FOUNDATION WALL BELOW)



PROJECT	KEHL STREET TOWNHOMES BLOCK-E 242 KEHL STREET, KITCHENER, ONTARIO	TITLE	MAIN FLOOR PLAN INTERIOR UNITS 32, 33	STATUS: BUILDING PERMIT	
				PLOTTED: 3/10/20158:42 AM	SCALE: 3/16"=1'-0"
SHEET No.	A3.05			DWN BY: BAM	
				DATE: MARCH 2015	
				REV.	
					
				<p>I, Carrie McMillan, review and take responsibility for the design work on behalf of our firm Orchard Design Studio Incorporated registered under Division C, Part 3 (3.2.4) of the Building Code. I am qualified, and the firm is registered, in the appropriate classes/categories. Firm BCIN: 28615 Individual BCIN: 32875</p> <p>Signed: _____</p>	
				 ORCHARD DESIGN STUDIO INCORPORATED (519) 620-0414	